

SLUM REHABILITATION AUTHORITY

No: SRA/Maint. Sec./Desk-1/ 10 /2024

Date: 01-03-2024

E-QUOTATION NOTICE FOR E-TENDER

1. Quotations in sealed covers are invited from the Contractors so as to reach the office of the undersigned at Slum Rehabilitation Authority, Administrative Bldg., Anant Kanekar Marg, Bandra (E), Mumbai- 400 051. **on or before 07/ 03/2024 upt 3.00 p.m. for the work of Repairing and replacing old damaged ply partition and storage on 3rd floor Secretary sir's Ante chamber and P.A's Cabin at Slum Rehabilitation Authority, Administrative building, Bandra (East), Mumbai-400051.**
2. **The estimated cost of the work is Rs. 1,28,326/-** (Rupees one lakhs twenty eight thousand three hundred and twenty six only).
3. The quotations in sealed cover shall be addressed to the Executive Engineer Maint/SRA, Slum Rehabilitation Authority, Administrative Bldg., Anant Kanekar Marg, Bandra (E), Mumbai- 400 051. The blank quotations can be downloaded from the tender section of SRA website www.sra.gov.in from **01 / 03/2024** to **07 /03 /2024** upto **3.00 p.m.**
4. The quotationer shall quote in ink his percentage offer above/below or at par the estimated cost both in figures and words. The quotation should be submitted in a single sealed Envelope containing forwarding letter, quotation notice and duly filled Schedule-B and signed on each page.
5. The name of work for which quotations have been given should be stated clearly on the envelope containing the quotation and name of Contractor should be written on lower left of envelope.
6. The sealed quotation will be received by the office of Executive Engineer Maint./SRA, Slum Rehabilitation Authority, Administrative Bldg., Anant Kanekar Marg, Bandra (E), Mumbai- 400 051. upto **3.00 p.m.** by **07/03/2024** and will be opened at **3.30 p.m.** on the same day as far as possible in the presence of the contractors/their representatives whosoever remain present at that time.
7. The quantities as shown in Schedule 'B' are approximate. The payment will be made as per actual quantity of work done.
8. The acceptance of quotation shall rest with the competent authority who reserves the right to reject any or all the quotations without assigning any reason for doing so.
9. The quotation submitted by the quotationer shall be binding on him for a period of 60 days from the last date of receipt of quotation.
10. No alternation in the form of quotation or schedule of quantities, specifications shall be entertained.
11. The entire work is to be completed within **30 days**.
12. The work shall be carried out in accordance with I.S. specifications for the particular items and as per the detailed specifications mentioned in Schedule-B.
13. The rates quoted shall be inclusive of all taxes, Octroi Duty and free delivery at site of work and nothing extra shall be paid on any account.

14. The quotationer is advised to visit and examine the site of work and its surroundings before quoting the rate and acquaint themselves with the site conditions.
15. The contractor will have to make his/ their own arrangement at his/their cost for office and stores and safeguard the materials brought on the work and the materials issued by the department if any.
16. The contractor shall provide all labours, tools, pegs, watering and all other materials as required for line out and setting out the layout etc. for the work without claiming any payment.
17. After the completion of the work, the contractor shall remove forthwith all his/ their serviceable and un-serviceable materials from site of work and other debris shall be dumped and levelled as ordered within the scope of work if so ordered without any extra cost.
18. No escalation shall be paid to the contractor.

Sd/-

Executive Engineer
Slum Rehabilitation Authority

Issued to:

M/s. _____

Copy to F.C/SRA for information.

Copy to A.E/ SRA, for information and necessary action.

Copy to notice board/SRA.

Copy to information technology department/SRA. For publishing quotation notice along with Abstract on SRA website



SLUM REHABILITATION AUTHORITY

No: SRA/MAINT.SEC./DESK-1/10/2024

Date: 01-03-2024

Abstract

Subject: Repairing and replacing old damaged ply partition and storage on 3rd floor Secretary sir's Ante chamber and P.A's Cabin at Slum Rehabilitation Authority, Administrative building, Bandra (East), Mumbai-400051.

Sr. No.	Description	Rates (rs)	Quantity	Unit	Amount (rs)
<u>Item No.01</u>	Removing the existing cement plaster of any thickness without causing dust nuisance and stacking the debris upto a distance of 50 metres or spreading in the compound and cleaning the site etc. complete.	54.60	8.75	sq.mt	477.75
<u>Item No.02</u>	Removing wooden or A.C. partition including frame work and stack-ing the materials as with all leads, lifts etc. complete.	42.00	9.81	sq.mt	412.02
<u>Item No.03</u>	Providing and laying vitrified matt finish tiles having size 590mm to 605 mm x to 605 mm of 8 to 10 mm thickness and confirming IS. 15622-2006 (Group Bla) of approved make, shade and pattern for flooring in required position laid on a bed of 1:4 cement mortar including neat cement float, filling joints, curing and cleaning etc. complete.	1680	8.75	sq.mt	14700.00
<u>Item No.04</u>	Providing and applying plaster / wall punning with plaster of paris (with plaster of paris material) in 10 to 13 millimeter thickness to previously plastered surface / or on newly brick surface (Excluding rough cast plaster) in all position including preparing and finishing the surface scaffolding etc. complete.	600.6	8.75	sq.mt	5255.25
<u>Item No.05</u>	Providing and applying Royale Luxury Emulsion of approved make on internal wall surface as detailed below Scrapping for surface with emery paper and wipe clean for area. wall primer with brush by adding mineral turpentine oil by 8 to 10 % or water by 15 to 20% allowing to dry for 6 to 8 hours After applying acrylic wall putty with appropriate proportion of water of allow to dry for period of 4 to 6 hours of activity. Scrapping with emery paper and wipe clean Applying paints Royale Luxury emulsion 1st coat with brush water content water 40 to 45% or 65 to 70% by roller Applying paints Royale luxury emulsion 2nd coat with brush with water content 40 to 45% or 65 to 70 % by roller. (With prior approval of S.E.)	288.75	20.66	sq.mt	5965.58

<u>Item No.06</u>	proviidng and fixing low height partitions at required location having minimum 65 mm thick made by using 50 x 50 mm (finished size) centrally providence teak wood (CPTW) Section framiong at 600 mm center to center with 6 mm marine ply etc complete work as directed by the engineer incharge.	6684.00	7.76	sq.mt	51867.84
<u>Item No.07</u>	Providingand applying french polish to newwood work, for required finishing including. knotting, preparing the surfaces, scaffolding etc. complete as directed. Bd.N.1.3 Page One Number 399 One Square Metre 241 192 1066 Wood Finish 34.07 BDN 1.4 Providing and applying varnish in one coat on previously varnished wood work including knotting, preparing the surface, scrapping, scaffold	253.05	13.99	sq.mt	3540.17
<u>Item No.08</u>	Low Height Storage - providing and fixing on site 40 cm Deep Low Height Storage Unit at required location less than 1.35 meter height by using 19mm marine ply of requisite etc complete work as directed by engineer incharge.	12695.00	2.09	sq.mt	26532.55
Total					108751.15
CGST 9%					9787.60
SGST 9%					9787.60
Total Amount					128326.36
Say Rupees 1,28,326/-					

I/We hereby agree to quote _____% Above/Below or At Par with the estimated cost put to the tender. Therefore, the amount _____ (in words)

_____.

Sd/-

Executive Engineer
Slum Rehabilitation Authority